builder: **SAMPLE BUILDERS** load 2 of 6

lot / job: **WEYCROFT** 10400

materials this load - 1st floor 3/4tg thru 1st floor ceiling

see separate sheet for glue, housewrap, window poly, nails, hangers, flashing, etc

qty	item	unit price	amount
46	21010sp		
2	21012sp		
81	21014sp		
87	21016sp		
builder must confirm stud height			
78	2x4 garage studs		
412	24105precuts		
168	2414sp		
10	2416sp		
3	2616sp		
10	2620sp		
8	2816sp		

qty	item	unit price	amount
58	3/4tg -----		
110	7/16osb		
wall sheathing - confirm material			
2	lvl 11.875x06'		
2	lvl 11.875x12'		
2	lvl 16x18'		
2	lvl 9.25x06'		
7	lvl 9.25x08'		
5	lvl 9.25x10'		
2	lvl 9.25x14'		
2	lvl 9.25x16'		

$ **add estimated cost to framing budget**

dashed lines indicate a tray ceiling at the

DINING ROOM

no materials are included for these structurals

add as needed - ship at backframe