

builder: **SAMPLE BUILDERS**

lot / job: **WEYCROFT**

10400

phase: **load 5 of 6**

**FRONT PORCH**

qty item unit price amount qty item unit price amount

**front porch materials**

**If mixed with the main framing order, porch materials are very likely to have been used for something else by the time they are needed**

**To help prevent this, the porch materials are listed as a separate load**

**see cutlist items beginning**

**F**

**\*\*\* posts to ground, lateral bracing, and step materials are not included - add as needed**

**add 7/16OSB for temporary safety flooring if needed**

**note - add material as needed if the porch beam needs to be "packed-out" for architectural detailing**

**joists are assumed to be hangered or ledgered to the treated band of the house - a second treated band is not included unless called out specifically**

**note - no finished flooring is included**

**structure only - see notes at left**

4 21008sp

2 21024sp

6 2612sp

6 2614sp

1 15 felt

12 2608sp

12 2610sp

2 2812sp

8 7/16osb