builder: **SAMPLE BUILDERS** | load 6 of 6

lot / job: **WEYCROFT** | 10400

materials this load - rafters, hips, ridges, valleys, roof sheathing, felt

see separate sheet for glue, housewrap, window poly, nails, hangers, flashing, etc

qty	item	unit price	amount
9	15felt		
6	21008sp		
2	21010sp		
5	21012sp		
1	21014sp		
4	21016sp		
2	21018sp		
3	21020sp		
24	2414sp		
2	2608sp		
8	2610sp		
2	2614sp		
32	2616sp		
1	2618sp		
2	2622sp		
4	2624sp		
58	2810sp		
5	2812sp		
25	2814sp		
39	2816sp		
5	2818sp		
23	2820sp		
41	2822sp		
19	2824sp		

qty	item	unit price	amount
$	**add estimated cost to framing budget**		
	a substantial amount of material may be		
	needed for temporary scaffolding to erect		
	the roof system - no specific material is		
	included for that purpose		
141	7/16osb		
1	lvl 11.875x14'		
2	lvl 11.875x22'		
96	2414sp		
	material for short kneewalls, plates,		
	gable framing, stiffeners, strongbacks,		
	and tie-downs needed to level the rafter		
	ends and facias - adjust this amount		
	as needed before shipment		