

builder: **SAMPLE BUILDERS**

lot / job: **WEYCROFT**

10389

phase:

load 5 of 6

SCREENED PORCH

qty	item	unit price	amount	qty	item	unit price	amount
screened porch materials				note - no finished flooring is included			
If mixed with the main framing order, porch materials are very likely to have been used for something else by the time they are needed				structure only - see notes at left			
To help prevent this, the porch materials are listed as a separate load				2	21008sp		
see cutlist items beginning				3	21012sp		
sc				2	21014sp		
*** posts to ground, lateral bracing, and step materials are not included - add as needed				1	2808sp		
add 7/16OSB for temporary safety flooring if needed				11	2814sp		
note - add material as needed if the porch beam needs to be "packed-out" for architectural detailing				25	tr21012		
joists are assumed to be hangered or ledgered to the treated band of the house - a second treated band is not included unless called out specifically				6	tr21014		
				4	tr2416		
				1	15felt		
				1	21014sp		
				7	2610sp		
				20	2612sp		
				12	7/16osb		